



Report of Load Test

Report Number: 55108-g	Job Number: 55108	Load Test Certificate. Page1	Date of Report: 19/06/2018	Date of Load Test: 19/07/2018
---------------------------	----------------------	-------------------------------------	-------------------------------	----------------------------------

Name and address of customer for whom the test was made: Vertical Leisure Ltd Unit 2, 181 Victoria Road New Barnet Herts	Address of premises at which the examination was made: Bickers Lifting Ltd Ivy Farm Works Coddendam Suffolk
--------------------------------------------------------------------------------------------------------------------------------------	-------------------------------------------------------------------------------------------------------------------------

Item ID/ Asset No	Product/Product Description	Working Load Limit	Date of Last thorough Examination	Additional Notes
XFP-45ST-BSC	X-Fly Fly Pole Set - Basic (ST)	TBC	N/A	

Measuring Equipment Used: RLPT5 5t Loadcell. Serial No. 16155. Calibrated 18-10-17. cert No. 14749

Notes: Test Scenario: X-Fly Fly Pole Set - Basic (ST) will have a tensile load applied along its length

Name of Report Maker: Darren Short	Authenticator Signature: <i>M. Ford</i>	Name of person authenticating this report: Marina Ford
-------------------------------------------	------------------------------------------------	---------------------------------------------------------------

Name and address of employer of persons making and authenticating this report: Bickers Lifting Ltd, Ivy Farm works, High Street, Coddendam, Suffolk. IP6 9QX

Bickers Lifting Ltd, Ivy Farm works, High Street, Coddendam, Suffolk. IP6 9QX. Registered in England 3830215.	Tel: 01449
761 705	www.bickerslifting.co.uk
	sales@bickerslifting.co.uk



Report of Load Test

Report Number: 55108-g	Job Number: 55108	Detailed Results. Page 2	Date of Report: 19/06/2018	Date of Load Test: 19/07/2018
Name and address of customer for whom the test was made: Vertical Leisure Ltd Unit 2, 181 Victoria Road New Barnet Herts		Address of premises at which the examination was made: Bickers Lifting Ltd Ivy Farm Works Coddham Suffolk		
Item ID/ Asset No	Product/Product Description	Working Load Limit	Date of Last thorough Examination	Additional Notes
XFP-45ST-BSC	X-Fly Fly Pole Set - Basic (ST)	TBC	N/A	

Test Details:

X-Fly Fly Pole Set - Basic (ST) will be placed in the tensile test rig and a load applied at each end. load applied incrementally and deflection and permanent set measured

Results:

Weight Applied (KGs)	Deflection (mm)	Permanent Set (mm)	Notes
100	0	0	
250	0	0	
446	0	0	
796	0	0	
3300	0	2	at joint
3300	No Deflection of pole - failed due to joining pin snapped		